

**Short Tender Notice: Repairing & Renovation of Portion of Compound Wall between
Type-V Quarter and Girls Hostel at New Campus of CIFE, Mumbai.**

Tel.No.26361446/7/8

Fax No.26361573

**Central Institute of Fisheries Education
(Deemed University, ICAR)
Versova, Mumbai - 400 061**

F. No. 32(164)/Works/2016-17/F-39

Date: 20.12.2016

Short Tender Notice

Quotations are invited in sealed envelope from eligible and approved Govt. registered contractors i.e. CPWD/ PWD/ BSNL/ MTNL etc. for work titled. Quotations duly completed in all respects shall be received up to 1500 hrs. on 10.01.2017 and the same shall be opened at 1530 hrs. on 10.01.2017 Quoted rates must be valid for one year from the date of acceptance of the quotation.

Interested contractors may download the quotation from our website <http://www.cife.edu.in>.

Quotations received after the due date and time will not be entertained. The Director of the institute reserves the right to accept or reject any or all quotations without assigning any reasons whatsoever. No correspondence shall be entertained in this regard.

Senior Administrative Officer



ICAR-CENTRAL INSTITUTE OF FISHERIES EDUCATION
(DEEMED UNIVERSITY)
Off. Yari Road, Seven Bungalow, Versova, Andheri (W)
Mumbai – 400 061

Tel: 022 -26361446/7/8

Website: www.cife.edu.in

Fax: 022 -26361573



F. No. 32(164)/Works/2016-17/F-39

Date: 20.12 2016

To

Name of the work : Repairing & Renovation of Portion of Compound Wall between Type-V Quarter and Girls Hostel at New Campus of CIFE, Mumbai.

IMPORTANT DATES

Last date for receiving the quotations : Up to 1500 hrs. on 10 January, 2017

Date of opening of quotations : At 1530 hrs. on 10 January, 2017

Date of completion of work : 1 month from award of work

The following documents are to be enclosed along with the tender failing which the tender shall be rejected out rightly:

1. A copy of contractor's registration with CPWD/ PWD/ MES/ BSNL/ MTNL/ P & T/ All India Radio/ PSU/ Any Other Govt. Organizations
2. A copy of PAN Card
3. A Photostats (i. e Xerox) copy of blank cheque for making payment by RTGS method.

INSTRUCTIONS TO BIDDERS, TERMS & CONDITIONS OF CONTRACT FOR EXECUTION OF WORKS

1. Quotations must be addressed to **The Director, Central Institute of Fisheries Education (Deemed University, ICAR), Panch Marg, opposite Panchvati Building, Off. Yari Road, Versova, Andheri (W), Mumbai - 400 061**

2. Quotations must be submitted either by registered/speed post or may be dropped in the tender box placed in the office of the OIC (Works)/ Senior Administrative Officer, CIFE, Mumbai in a sealed cover super scribing on it the name of work for which the quotation is called for and also the date & time of submission.
3. Quotations received after due date and time shall not be entertained.
4. The quoted rates must be valid for one year.
5. Contractor/ agency should be experienced in above said work.
6. The quotation should be accompanied by an Earnest Money Deposit (EMD) amounting to **Rs.11,700/- (Rupees Eleven thousand seven Hundred Only)** in the form of crossed demand draft drawn in favour of "**ICAR Unit, CIFE, Mumbai**".
7. The EMD of successful bidder shall be converted into a part of security deposit. The EMD of unsuccessful bidders will be returned within 15 days from the date of award of work to successful bidder.
8. The successful bidder has to pay Security Deposit amounting to 10% of the quoted amount. The security deposit will be released only after six months from the date of successful completion of work.
9. The defect liability period is 6 months. Any defect arising in the defect liability period is to be rectified by the contractor without any extra cost, failing which the same shall be done departmentally at the "**risk and cost**" of the contractor and the amount of expenditure shall be deducted from the security deposit.
10. The quoted rates should be inclusive of cost of material, carriages, all taxes whatsoever, storage, watch and ward, wastages, etc. The quoted rates shall not be increased under any circumstances.
11. Income tax will be deducted at source from the bill as per rules.
12. The Institute will not supply any tools, equipments, materials. The contractor has to make their own arrangement.
13. The EMD submitted by the bidder is liable to be forfeited by the Institute, if the selected firm/bidder fail to commence the work within seven days from the date of receipt of work order.

14. The work must be completed within the specified time period, failing which a penalty up to 5% of the tendered amount per month will be charged.
15. Works are to be executed strictly as per the specifications mentioned in the tender document failing which work shall be rejected.
16. The material used for renovation must be approved by the officer In-charge (Works)/ site in-charge before using failing which works shall be rejected.
17. The agency has to abide by all rules and regulations pertaining to labour act. The contractor has to take all necessary steps for the welfare measures of labours employed by him at the site.
18. The agency will be fully responsible for providing medical facilities to their labourers in case of any accident, etc. Matters related to labour welfare/problems should be dealt by the contractor only. CIFE, Mumbai shall not be responsible in such matters.
19. Taxes, if any, should be clearly mentioned in the quotation, failing which it will be presumed that the quoted rates are inclusive of all taxes. No additional tax will be allowed if the same is not mentioned in the quotation document.
20. The tenders/bidders in their own interest are instructed to visit the site for understanding the site conditions, nature of work, etc.
21. The Director, CIFE, Mumbai reserves the right to accept or reject any or all tender / all tenders without specifying any reason whatsoever. No correspondence shall be entertained in this regard. The decision of the Director, CIFE, Mumbai shall be final and binding on all concerned in such matters.

Yours faithfully,

Senior Administrative Officer

Enclosed: BOQ with technical specifications.

**CENTRAL INSTITUTE OF FISHERIES EDUCATION (DEEMED UNIVERSITY, ICAR), MUMBAI –
400 061**

SCHEDULE

NAME OF THE WORK: Repairing & renovation of portion of compound wall between Type-V quarter and girls hostel at new campus of CIFE, Mumbai.

SN.	Details of works	Qty	Unit	Rate	Amount
1	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth upto 30 cm measured at a height of 1m above ground level and removal of rubbish upto a distance of 50 m outside the periphery of the area cleared.	200.00	SQM		
2	Centering and shuttering including strutting, propping etc. and removal of form for :(a) Walls (any thickness) including attached pilasters, butteresses, plinth and string courses etc.	50.00	SQM		
3	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement, with 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size).	6.00	CUM		
4	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level.	375.00	kg		
5	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in :(a)Cement mortar 1:4 (1 cement : 4 coarse sand)	15.00	CUM		
6	18 mm cement plaster in two coats under layer 18 mm thick cement plaster 1:5 (1 cement : 5 coarse sand) finished with a top layer 6 mm thick cement plaster 1:6 (1 cement : 6 fine sand).	300.00	SQM		
7	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :(A)1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	4.00	CUM		
8	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	250.00	kg		

9	Finishing walls with Acrylic Smooth exterior paint of required shade :(a) New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20kg/ 10 sqm)	300.00	SQM		
10	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade:(a)Two or more coats on new work	50.00	SQM		
11	Providing and fixing double scaffolding system (cup lock type) on the exterior side, up to seven story height made with 40 mm dia M.S. tube 1.5 m centre to centre, horizontal & vertical tubes joining with cup & lock system with M.S. tubes, M.S. tube challies, M.S. clamps and M.S. staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for the required duration as approved and removing it there after .The scaffolding system shall be stiffened with bracings, runners, connection with the building etc wherever required for inspection of work at required locations with essential safety features for the workmen etc.complete as per directions and approval of Engineerin-charge .The elevational area of the scaffolding shall be measured for payment purpose .The payment will be made once irrespective of duration of scaffolding	240.00	SQM		
12	Dismantling steel work in built up sections in angles, tees, flats and channels including all gusset plates, bolts, nuts, cutting rivets, welding etc. including dismembering and stacking within 50metres lead.	400.00	kg		
13	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	90.00	SQM		

14	Providing and fixing concertina coil fencing with punched tape concertina coil 600 mm dia 10 metre openable length (total length 90 m), having 50 nos rounds per 6 metre length, upto 3 m height of wall with existing angle iron 'Y' shaped placed 2.4 m or 3.00 m apart and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I. staples and G.I. clips to retain horizontal, including necessary bolts or G.I. barbed wire tied to angle iron,all complete as per direction of Engineer-in-charge, with reinforced barbed tape(R.B.T.) / Spring core (2.5mm thick) wire of high tensile strength of 165 kg/ sq.mm with tape (0.52 mm thick) and weight 43.478 gm/ metre (cost of M.S. angle, C.C. blocks shall be paid separately)	65.00	metre		
				Total in Rs.	
				Taxes if any	
				Grand Total	

Amount in words(Rupees _____)

Date:

Sign of bidder with seal